

DIVERSION STRUCTURE



Screen was installed in the fall of 2006. A crew from WDFW's Yakima Construction Shop assisted with the screen installation. The site was well prepared and installation was relatively straight foreword. The project was fund by SRFB through the NYCD. Paul Cleary and Mike Hey were the engineers on this project. The modular rotary wiper fish screen was furnished by WDFW with funding from the National Marine Fisheries Service. The plate screen is designed to for the one (1) cfs water right. There should be twelve inches (12") of water depth (submergence) on the screen surface to meet current state and federal fish screening criteria. The bypass section is approximately 60 feet long and enters the screen below a root wad. Access to the site is off the S.F. Ahtanum road.

